

# Discharge Report

**Workspace: 72438-1RiempFSRU-3R**

**Study: Riempimento FSRU-ME4**

**Equipment Item: 3R Collettore GNL riempimento FSRU**

72438-1RiempFSRU-3R\Riempimento FSRU-ME4\3R Collettore GNL riempimento FSRU

Material	GAS NATURALE	
East	0	m
North	0	m

## Scenario (Leak) : 120mm

72438-1RiempFSRU-3R\Riempimento FSRU-ME4\3R Collettore GNL riempimento FSRU\120mm

**Weather: Category 2/F**

### INPUT DATA

#### Inventory data

Mass in vessel	<b>38799,7</b>	kg
----------------	----------------	----

#### Stagnation Data (upstream end for long pipe)

Initial pressure (gauge)	<b>5</b>	bar
Initial temperature	<b>-160</b>	degC
Fluid state	<b>Non-saturated liquid</b>	

#### Scenario data

Phase to be released	Liquid	
Tank head	0	m
Hole diameter	<b>120</b>	mm
Discharge coefficient	<b>0,62</b>	fraction

### OUTPUT DATA

Mass flow rate	149,509	kg/s
Release duration	259,514	s

### Orifice or pipe exit data (before atmospheric expansion)

Pressure	1,01325	bar
Temperature	-160,121	degC
Liquid mass fraction	<b>1</b>	fraction
Velocity at vena contracta (at exit for pipe releases)	46,8731	m/s
Discharge coefficient	0,62	

### Final Data (after atmospheric expansion)

Temperature	-160,343	degC
Liquid mass fraction	0,998608	fraction
Droplet diameter	319,833	um
Expanded diameter	<b>0,108111</b>	m
Velocity	46,8731	m/s

## Weather: Category 5/D

### INPUT DATA

#### Inventory data

Mass in vessel	<b>38799,7</b>	kg
----------------	----------------	----

#### Stagnation Data (upstream end for long pipe)

Initial pressure (gauge)	<b>5</b>	bar
Initial temperature	<b>-160</b>	degC
Fluid state	<b>Non-saturated liquid</b>	

#### Scenario data

Phase to be released	Liquid	
Tank head	0	m
Hole diameter	<b>120</b>	mm
Discharge coefficient	<b>0,62</b>	fraction

### OUTPUT DATA

Mass flow rate	149,509	kg/s
Release duration	259,514	s

#### Orifice or pipe exit data (before atmospheric expansion)

Pressure	1,01325	bar
Temperature	-160,121	degC
Liquid mass fraction	<b>1</b>	fraction
Velocity at vena contracta (at exit for pipe releases)	46,8731	m/s
Discharge coefficient	0,62	

#### Final Data (after atmospheric expansion)

Temperature	-160,343	degC
Liquid mass fraction	0,998608	fraction
Droplet diameter	319,833	um
Expanded diameter	<b>0,108111</b>	m



Velocity	46,8731	m/s
----------	---------	-----

