

Input Report

Workspace: 72438-1RiempFSRU-3R

Riempimento FSRU-ME4

Study

72438-1RiempFSRU-3R

Tab	Group	Field	Value	Units
Context of calculations	Selection of context	Weathers to use for this study	Weather folder	
		Parameters to use for this study	Parameter set ME4	
		Obstructions to use for this study	Multi-Energy obstruction set	
Bund, building and terrain	Terrain and bund definition	Type of terrain for dispersion	Default terrain	
		Type of pool substrate and bunds	No bund	
Toxic parameters	Indoor toxic calculations	Specify the downwind building type	Unselected	
		Building type (downwind building type)	Buildings\Building type	
Dispersion	Distances of interest	Distances of interest		m

3R Collettore GNL riempimento FSRU

Pressure vessel

72438-1RiempFSRU-3R\Riempimento FSRU-ME4

Tab	Group	Field	Value	Units
Material	Material	Material	GAS NATURALE	
		Specify volume inventory?	Yes	
		Mass inventory	38799,7	kg
		Volume inventory	85,33	m3
		Material to track	GAS NATURALE	
	Phase	Specified condition	Pressure/temperature	
		Temperature	-160	degC
		Pressure (gauge)	5	bar
		Fluid state	Liquid	
		Liquid mole fraction	1	fraction
Scenario	Pipe dimensions	Pipe length		m
	Release location	Elevation	12,5	m
		Tank head	0	m
	Direction	Outdoor release direction	Down - impinging on the ground	
		Outdoor release angle	0	deg
Discharge parameters	Model settings	Atmospheric expansion method	DNV recommended	
		Phase change upstream of orifice?	Disallow liquid phase change only (metastable liquid)	
	Droplet break-up mechanism	Droplet break-up mechanism - instantaneous	Use flashing correlation	
		Droplet break-up mechanism - continuous	Do not force correlation	

Short pipe	Pipe characteristics	Pipe roughness	0,045	mm
	Frequencies	Frequency of bends in pipe	0	/m
		Frequency of couplings in pipe	0	/m
		Frequency of junctions in pipe	0	/m
	Frequencies of valves	Frequency of excess flow valves	0	/m
		Frequency of non-return valves	0	/m
		Frequency of shut-off valves	0	/m
	Velocity head losses	Excess flow valve velocity head losses	0	
		Non-return valve velocity head losses	0	
		Shut-off valve velocity head losses	0	
Time varying releases	Modelling of time-varying leaks and line ruptures	Vacuum relief valve	Operating	
		Vacuum relief valve set point	0	bar
	Inventory data for time-varying releases	Tank volume	85,33	m ³
		Tank vapour volume	0	m ³
		Tank liquid volume	85,33	m ³
		Tank liquid level	0,485968	m

		Maximum vapour release height	0,6	m
		Minimum mass inventory	0,1	kg
		Maximum mass inventory	1E+09	kg
	Safety system modelling for time-varying releases	Safety system modelling (isolation and blowdown)	No	
Dispersion	Dispersion scope	Concentration of interest		ppm
		Averaging time for concentration of interest		
		Specify user-defined averaging time	No	
		User defined averaging time		s
	Distances of interest	Distances of interest		m
	Averaging time for reports	ERPG [1 hr]	No	
		IDLH [30 mins]	No	
		STEL [15 mins]	No	
Bund, building and terrain	Terrain and bund definition	Type of terrain for dispersion	Default terrain	
		Type of pool substrate and bunds	No bund	
	Building definition	Release building		
		In-building release?	Outdoor	
		Building wake effect	None	
		Wind or release	0	deg

		angle from North		
		Handling of droplets	Trapped	
		Indoor mass modification factor	3	
Explosion parameters	Explosion method (Consequence calculations only)	Explosion method	Multi-Energy: Uniform confined	
	Ignition	Supply late ignition location	No ignition location	
		Location of late ignition		m
	Vapour liquid method	Use explosion mass modification factor	Yes	
		Explosion mass modification factor	3	
Fireball	Result types to calculate	Calculate probit	No	
		Calculate dose	No	
		Calculate lethality	No	
	Radiation levels	Number of input radiation levels	3	
		Intensity levels	4; 12,5; 37,5	kW/m2
		Probit levels	2,73; 3,72; 7,5	
		Dose levels	1,27E+06; 5,8E+06; 2,51E+07	
		Lethality levels	0,01; 0,1; 0,99	fraction
	Parameters	Mass modification factor	3	
		Fireball maximum exposure	20	s

		duration		
	Calculation method	Fireball model	Martinsen time varying	
		TNO model flame temperature	1726,85	degC
Jet fire	Jet fire method	Jet fire method	Cone model	
	Result types to calculate	Calculate probit	No	
		Calculate dose	No	
		Calculate lethality	No	
	Radiation levels	Number of input radiation levels	5	
		Intensity levels	3; 5; 7; 12,5; 37,5	kW/m2
		Probit levels	2,73; 3,72; 7,5	
		Dose levels	1,27E+06; 5,8E+06; 2,51E+07	
		Lethality levels	0,01; 0,1; 0,99	fraction
	Parameters	Rate modification factor	3	
		Jet fire maximum exposure duration	20	s
	Cone model data	Horizontal options	Use standard method	
		Correlation	Recommended	
		Flame-shape adjustment if grounded	Yes	
	Surface emissive power	Calculation method for surface emissive power	Calculate SEP	
		Flame emissive power		kW/m2
		Emissivity fraction		fraction
Pool fire	Result types to	Calculate probit	No	

	calculate			
		Calculate dose	No	
		Calculate lethality	No	
	Radiation levels	Number of input radiation levels	5	
		Intensity levels	3; 5; 7; 12,5; 37,5	kW/m2
		Probit levels	2,73; 3,72; 7,5	
		Dose levels	1,27E+06; 5,8E+06; 2,51E+07	
		Lethality levels	0,01; 0,1; 0,99	fraction
	Parameters	Radiative fraction for general fires	0,4	fraction
		Pool fire maximum exposure duration	20	s
Geometry	Geometry	East	0	m
		North	0	m

120mm

Leak

72438-1RiempFSRU-3R\Riempimento FSRU-ME4\3R Collettore GNL riempimento FSRU

Tab	Group	Field	Value	Units
Scenario	Hole	Orifice diameter	120	mm
		Use specified discharge coefficient?	Yes	
		Discharge coefficient	0,62	fraction
	Release location	Elevation	12,5	m
		Tank head	0	m
	Direction	Outdoor release direction	Down - impinging on the ground	
		Outdoor release angle	0	deg
Material	Material	Material characteristics	Flammable only	
		Material to track	GAS NATURALE	
		Type of risk effects to model	Flammable only	
	Phase	Phase to be released	Liquid	
Discharge parameters	Model settings	Atmospheric expansion method	DNV recommended	
		Phase change upstream of orifice?	Disallow liquid phase change only (metastable liquid)	
	Droplet break-up mechanism	Droplet break-up mechanism - continuous	Do not force correlation	
Dispersion	Dispersion scope	Concentration of interest		ppm
		Averaging time for concentration of interest		
		Specify user-defined	No	

		averaging time		
		User defined averaging time		s
	Distances of interest	Distances of interest		m
	Averaging time for reports	ERPG [1 hr]	No	
		IDLH [30 mins]	No	
		STEL [15 mins]	No	
Bund, building and terrain	Terrain and bund definition	Type of terrain for dispersion	Default terrain	
		Type of pool substrate and bunds	No bund	
Explosion parameters	Explosion method	Explosion method	Multi-Energy: Uniform confined	
	Ignition	Supply late ignition location	No ignition location	
		Location of late ignition		m
	Vapour liquid method	Use explosion mass modification factor	Yes	
		Explosion mass modification factor	3	
Fireball	Result types to calculate	Calculate probit	No	
		Calculate dose	No	
		Calculate lethality	No	
	Radiation levels	Number of input radiation levels	3	
		Intensity levels	4; 12,5; 37,5	kW/m2
		Probit levels	2,73; 3,72; 7,5	
		Dose levels	1,27E+06; 5,8E+06; 2,51E+07	
		Lethality levels	0,01; 0,1; 0,99	fraction
	Parameters	Mass modification factor	3	
		Fireball maximum	20	s

		exposure duration		
	Calculation method	Fireball model	Martinsen time varying	
		TNO model flame temperature	1726,85	degC
Jet fire	Jet fire method	Jet fire method	Cone model	
	Result types to calculate	Calculate probit	No	
		Calculate dose	No	
		Calculate lethality	No	
	Radiation levels	Number of input radiation levels	5	
		Intensity levels	3; 5; 7; 12,5; 37,5	kW/m2
		Probit levels	2,73; 3,72; 7,5	
		Dose levels	1,27E+06; 5,8E+06; 2,51E+07	
		Lethality levels	0,01; 0,1; 0,99	fraction
	Parameters	Rate modification factor	3	
		Jet fire maximum exposure duration	20	s
	Cone model data	Correlation	Recommended	
		Horizontal options	Use standard method	
		Flame-shape adjustment if grounded	Yes	
	Surface emissive power	Calculation method for surface emissive power	Calculate SEP	
		Flame emissive power		kW/m2
		Emissivity fraction		fraction
Pool fire	Result types to calculate	Calculate probit	No	
		Calculate dose	No	
		Calculate lethality	No	

	Radiation levels	Number of input radiation levels	5	
		Intensity levels	3; 5; 7; 12,5; 37,5	kW/m2
		Probit levels	2,73; 3,72; 7,5	
		Dose levels	1,27E+06; 5,8E+06; 2,51E+07	
		Lethality levels	0,01; 0,1; 0,99	fraction
	Parameters	Radiative fraction for general fires	0,4	fraction
		Pool fire maximum exposure duration	20	s

