

Technical drawing of a drainage system layout. The drawing shows a horizontal trench with a central section labeled "ASSE TOMBINO" (Trench Axis). The layout includes several components and dimensions:

- Left Section:** A "TOMBINO TM22 SCATOLARE 3.00x3.00m" (Manhole TM22 Box 3.00x3.00m) with a "PARAPETTO IN ACCIAIO" (Steel Parapet). The distance from the parapet to the manhole is "L=6.00m". The manhole is labeled "POZZETTO 3.00x4.00m".
- Central Section:** A long trench section labeled "ASSE TOMBINO" with a length of "L=21.10m". It contains two "TOMBINO 3.00x3.00 L=21.10m" (Manhole 3.00x3.00 L=21.10m).
- Right Section:** A "TOMBINO 3.00x3.00 L=21.60m" (Manhole 3.00x3.00 L=21.60m) followed by a "TRATTO CON GABBIONI L=6.00m" (Section with Gabions L=6.00m) and another "PARAPETTO IN ACCIAIO" (Steel Parapet).
- Dimensions:**
 - Vertical dimensions on the left: 1.00, 1.50, 1.50, 1.00, 5.50.
 - Horizontal dimensions: 3.80, 0.5, 0.5, 3.80.
 - Vertical dimensions on the right: 1.00, 1.50, 1.50, 1.00, 5.50.
- Labels:** "PARAPETTO IN ACCIAIO", "ASSE TOMBINO", "TOMBINO TM22 SCATOLARE 3.00x3.00m PK 7+375 (PANO)", "TOMBINO 3.00x3.00 L=21.10m", "TOMBINO 3.00x3.00 L=21.60m", "TRATTO CON GABBIONI L=6.00m", "POZZETTO 3.00x4.00m".

Technical drawing of a drainage system layout. The drawing shows a long trench with multiple inspection pits (POZZETTO) and manholes (TOMBO). Key components and dimensions include:

- POZZETTO DI ISPEZIONE** (Inspection Pit): Located at the start of the trench, with a width of 3.00x4.00m and a depth of 3.00m.
- TOMBO** (Manhole): Located at the end of the trench, with a width of 3.00x3.00m and a depth of 21.10m.
- PARAPETTO IN ACCIAIO** (Steel Parapet): Located at the end of the trench, with a height of 0.40m.
- GIUNTO WATERSTOP** (Waterstop Joint): Located at the junction of the inspection pit and the manhole.
- SCALA IN ACCIAIO ZINCATO** (Galvanized Steel Staircase): Located at the end of the trench, with a height of 1.68m.
- TRATTO CON GABBIONI** (Section with Gabions): Located at the end of the trench, with a length of L=6.00m.
- Dimensions**: The total length of the trench is 3.00x3.00m L=21.10m. The width of the trench is 3.00m. The depth of the trench is 21.10m. The drawing also shows various other dimensions for the inspection pit, manhole, and parapet.

Technical drawing of a U-shaped structure, likely a tomb, with dimensions and labels:

- Overall Width:** 4.00
- Overall Height:** 5.55
- Internal Width:** 3.00
- Internal Height:** 3.00
- Top Flange Width (each side):** 0.50
- Top Flange Thickness (each side):** 0.40
- Internal Vertical Dimension:** 2.55
- Internal Horizontal Dimension:** 4.52.75
- Labels:**
 - ASSE TOMBINO
 - PARAPETTO IN ACCIAIO

Technical drawing of a square tomb (ASSE TOMBO) showing dimensions and materials. The central square basin is 450x331 cm. The surrounding area is divided into a central square (3.00m x 3.00m) and four trapezoidal sections (1.00m x 1.00m). The total width and height are 4.00m. The drawing is labeled "ASSE TOMBO" and "MISTO CEMENTATO".

Technical drawing of a square table top. The drawing shows a square with a hatched pattern. The overall dimensions are 1040 mm by 1040 mm. The inner square has a side length of 800 mm. The hatched pattern is 20 mm thick. The drawing includes a section line labeled '43 SE TO BINO' and a dimension of 5.80 mm. The drawing is oriented vertically on the page.

Technical drawing of the 'SSE TOMBINO' cover, showing a top-down view with dimensions. The cover is rectangular with a central square opening. Dimensions include a total width of 4.80m, a central opening width of 3.00m, and a depth of 5.80m. A small detail '1:23' is shown near the bottom center.

20 120 20

CHIUSINO IN GHISA CARRABILE CLASSE D 400

20

ELEMENTO DI COPERTURA PREFABBRICATO

ELEMENTI DI PROLUNGA PREFABBRICATI

SCALA IN ACCIAIO ZINCATO

SOLETTA DI COPERTURA POZZETTO TOMBINO

VARIABLE

Technical drawing of a staircase showing two views: a side elevation and a front elevation.

Side Elevation (Left):

- Overall height: 2500
- Overall width: 1160
- Labels: ANELLI 40x5, MONTANTE SCALA 50x8, MONTANTI ANELLI 25x8, GRADINI Ø16
- Individual step height: 30
- Individual step width: 30

Front Elevation (Right):

- Labels: ANELLI 40x5, MONTANTI ANELLI, MONTANTE SCALA 50x8, GRADINI Ø16, SOSTEGNI SCALA 40x8
- Dimensions: 27, 5, 57, 89

Diagram illustrating the components of a glass partition system:

- RIEMPIMENTO**: Filling material (indicated by the dotted pattern in the panels).
- GIUNTO IMPERMEABILIZZANTE WATER STOP DA 20cm**: Waterproofing joint (indicated by the central vertical and horizontal lines).
- ARMATURA**: Reinforcement (indicated by the lines within the glass panels).

Diagramma di dettaglio della costruzione di un tetto a terrazza. La sezione trasversale mostra, dall'alto verso il basso:

- CAPPA DI PROTEZIONE 4cm
- RETE ELETTROSALDATA 105x10
- MASSETTO PER PENDENZA MIN. 5cm CON MAGRONE
- GEOTESSILE DI PROTEZIONE min. 600gr/mq
- GEOTESSILE DI BASE min. 600gr/mq
- MANTE IMPERMEABILE IN PVC Sps2mm
- SOLETTA TOMBINO

GETTO DI PULIZIA E LIVELAMENTO

- CONFORME ALLA UNA 111014
- CLASSE DI RESISTENZA MINIMA A COMPRESSIONE: C12/15
- DIMENSIONE MASSIMA DEGLI AGGREGATI: Dmax 40 mm

CALCESTRUZZO SCATOLARE E POZZETTO

- A PRESTAZIONE GARANTITA CONFORME ALLA UNA 111014
- CLASSE DI RESISTENZA MINIMA A COMPRESSIONE: C30/37
- CLASSE DI CONSISTENZA SLUMP: S4
- CLASSE DI ESPOSIZIONE: XC4-XA2
- DIMENSIONE MASSIMA DEGLI AGGREGATI: Dmax 32 mm
- RAPPORTO A/C MAX: 0.60
- CONTENUTO MINIMO DI CEMENTO 300 kg/mc
- COPRIFORRE: 45

ACCIAIO PER CEMENTO ARMATO IN BARRE

TIPO B450C CONTROLLATO IN STABILIMENTO SIALKABE
(PROPRIETÀ MECCANICA SECONDO UNI EN ISO 15630-2/2004)

- TENSIONE CARATTERISTICA DI SNERVIAMENTO: fyk > 450 MPa
- TENSIONE CARATTERISTICA DI ROTTURAZIONE: ftk > 540 MPa
- OGNI FORNITURA DEVE ESSERE ACCOMPAGNATA DA COPPIA CONFORME DEL RELATIVO CERTIFICATO, CON DATA NON ANTERIORE A TRE MESI, EMESSO DAL LABORATORIO UFFICIALE INCARICATO DEL CONTROLLO IN STABILIMENTO.

SPECIFICHE GENERALI

- CONTROLLO DI ACCETTAZIONE PER IL CALCESTRUZZO (D.M. 17/01/2018)
- TUTTE LE CARATTERISTICHE SONO INDICATE PER IL CALCESTRUZZO DEVONO ESSERE RIPRODURRE NEI DETTAGLI GENERALI
- E' VETATA QUALUNQUE AGGIUNTA D'ACQUA AL CALCESTRUZZO IN CANTIERE
- PRIMA DI GONFI GHIACCIALE DIREZIONE LAVORI
- IL GETTO CON TEMPERATURE DELL'ARIA SUPERIORE A 5°C DEVE ESSERE AUTORIZZATO DALLA DIREZIONE LAVORI STRUTTURALE
- IN FASE DI STAGIONAZIONE NON E' PERMESSO IL DILAVAMENTO SUPERFICIALE DEI GETTI PER PROGNA O RUSCELLAMENTO D'ACQUA
- IL GETTO DI STAGIONAZIONE DEI GETTI CON TEMPERATURE DELL'ARIA SUPERIORI A 25°C O IN PRESENZA DI FORTI IRRAZZIAMENTO SOLARE O DI VENTO
- PROTEZIONE A BADRAGNATA DELLE SUPERFICIE GUA INDURITE

PARAMETRI IN ACCIAIO S275

- MONTANTI IPEDIO
- ELEMENTI ORIZZONTALI TUBOLARI Ø44x 5prz26
- PIASTRA ANCORAGGIO 200x10x15
- INGHIASSAGGIO 4 TASSELLI M10

Key-Plan

COMUNE DI ARIEZZO

SVINCOLO "SAN GIULIANO"

SVINCOLO "ARIEZZO"

SVINCOLO "SAN ZENO"

SVINCOLO "SCOPETTONE"

SVINCOLO "STADIO"

LOTTO DI COMPLETAMENTO

LOTTO 1

VIA DELL'INDUSTRIA E DELL'ARTIGIANATO

VIA CASSIN

VIA CANTIERE

PRODOTTORE/DEVELOPPO

COMUNE DI ARIEZZO