

Tracciato: TR-A\_NV04B  
Sezione 1  
Progressiva: 0+00.00  
Scala: 1:200  
Quota di Riferimento: 30.00

QUOTE TERRENO		37.66	37.71	39.11	39.76	39.88	40.06	40.11
PROGRESSIVE TERRENO	-20.00	-17.23	-10.78	-7.52				15.00
QUOTE PROGETTO	38.99	38.99	37.34	37.17	37.09	37.06	37.21	40.06
DISTANZE PARZIALI PROGETTO	2.60	10.00	7.00	1.40	2.14	4.74	7.19	12.33
PROGRESSIVE PROGETTO	-20.00	-17.40	-7.00	0.00	1.41	3.70	7.19	15.00
DIFFERENZA QUOTE	1.34			-2.712				0.000

MOVIMENTI TERRA Prog. 0+00.00			
Area di sterro	61.90 m <sup>2</sup>		
Area di riparo	5.68 m <sup>2</sup>		
Volume sterro	0.00 m <sup>3</sup>		
Volume riparo	0.00 m <sup>3</sup>		
Volume sterro cumulato	0.00 m <sup>3</sup>		
Volume riparo cumulato	0.00 m <sup>3</sup>		
Volume netto	0.00 m <sup>3</sup>		
TERRENO VEGETALE			
Materiale	Area	Volume	Vol. Cum.
Veghiale	1.930 m <sup>2</sup>	0.00 m <sup>3</sup>	0.00 m <sup>3</sup>
SOVRASTRUTTURA			
Materiale	Area	Volume	Vol. Cum.
Ulcure	0.336 m <sup>2</sup>	0.00 m <sup>3</sup>	0.00 m <sup>3</sup>
Binder	0.420 m <sup>2</sup>	0.00 m <sup>3</sup>	0.00 m <sup>3</sup>
Base	1.009 m <sup>2</sup>	0.00 m <sup>3</sup>	0.00 m <sup>3</sup>
Fondazione	1.381 m <sup>2</sup>	0.00 m <sup>3</sup>	0.00 m <sup>3</sup>
Supercompattato	2.523 m <sup>2</sup>	0.00 m <sup>3</sup>	0.00 m <sup>3</sup>
Cist. Ulcure	0.075 m <sup>2</sup>	0.00 m <sup>3</sup>	0.00 m <sup>3</sup>
Cist. Binder	0.175 m <sup>2</sup>	0.00 m <sup>3</sup>	0.00 m <sup>3</sup>
Cist. Sottopav.	0.051 m <sup>2</sup>	0.00 m <sup>3</sup>	0.00 m <sup>3</sup>
Pad. Ulcure	0.105 m <sup>2</sup>	0.00 m <sup>3</sup>	0.00 m <sup>3</sup>
Pad. Magrone	0.175 m <sup>2</sup>	0.00 m <sup>3</sup>	0.00 m <sup>3</sup>
Pad. Allettamento	0.175 m <sup>2</sup>	0.00 m <sup>3</sup>	0.00 m <sup>3</sup>
MANUFATTI			
Materiale	Area	Volume	Vol. Cum.
Cunette	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	0.00 m <sup>3</sup>
Magrone Cunette	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	0.00 m <sup>3</sup>
Corsoio Rotatorio	0.054 m <sup>2</sup>	0.00 m <sup>3</sup>	0.00 m <sup>3</sup>
Quantità Fossati di Guardia			
Materiale	Area	Volume	Vol. Cum.
Rivestimento SX	0.24	0.00	0.00
Scavo Fossa SX	0.00	0.00	0.00
Rivestimento SX	0.24	0.00	0.00
Scavo Fossa SX	0.00	0.00	0.00

Tracciato: TR-A\_NV04B  
Sezione 4  
Progressiva: 0+060.00  
Scala: 1:200  
Quota di Riferimento: 30.00

QUOTE TERRENO		37.66	37.61	36.62	36.43	36.34	36.21
PROGRESSIVE TERRENO	-20.00	-16.74	-7.23	0.00	3.39	3.02	3.02
QUOTE PROGETTO	38.99	38.99	37.07	37.07	37.02	37.02	38.21
DISTANZE PARZIALI PROGETTO	2.60	10.00	7.00	2.91	3.69	5.65	10.05
PROGRESSIVE PROGETTO	-20.00	-17.40	-7.00	0.00	3.69	9.34	15.00
DIFFERENZA QUOTE	1.34		-1.360				0.000

MOVIMENTI TERRA Prog. 0+060.00			
Area di sterro	21.73 m <sup>2</sup>		
Area di riparo	7.00 m <sup>2</sup>		
Volume sterro	499.40 m <sup>3</sup>		
Volume riparo	39.23 m <sup>3</sup>		
Volume sterro cumulato	260.17 m <sup>3</sup>		
Volume riparo cumulato	91.51 m <sup>3</sup>		
Volume netto	2513.03 m <sup>3</sup>		
TERRENO VEGETALE			
Materiale	Area	Volume	Vol. Cum.
Veghiale	1.930 m <sup>2</sup>	21.79 m <sup>3</sup>	115.89 m <sup>3</sup>
SOVRASTRUTTURA			
Materiale	Area	Volume	Vol. Cum.
Ulcure	0.425 m <sup>2</sup>	14.43 m <sup>3</sup>	34.28 m <sup>3</sup>
Binder	0.532 m <sup>2</sup>	18.06 m <sup>3</sup>	42.65 m <sup>3</sup>
Base	1.276 m <sup>2</sup>	43.35 m <sup>3</sup>	102.84 m <sup>3</sup>
Fondazione	1.683 m <sup>2</sup>	24.34 m <sup>3</sup>	128.09 m <sup>3</sup>
Supercompattato	3.189 m <sup>2</sup>	108.31 m <sup>3</sup>	297.13 m <sup>3</sup>
Cist. Ulcure	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	2.73 m <sup>3</sup>
Cist. Binder	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	6.38 m <sup>3</sup>
Cist. Sottopav.	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	1.69 m <sup>3</sup>
Pad. Ulcure	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	4.31 m <sup>3</sup>
Pad. Magrone	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	7.18 m <sup>3</sup>
Pad. Allettamento	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	7.18 m <sup>3</sup>
MANUFATTI			
Materiale	Area	Volume	Vol. Cum.
Cunette	0.339 m <sup>2</sup>	4.12 m <sup>3</sup>	4.12 m <sup>3</sup>
Magrone Cunette	0.142 m <sup>2</sup>	1.75 m <sup>3</sup>	1.75 m <sup>3</sup>
Corsoio Rotatorio	0.054 m <sup>2</sup>	0.00 m <sup>3</sup>	2.07 m <sup>3</sup>
Quantità Fossati di Guardia			
Materiale	Area	Volume	Vol. Cum.
Rivestimento SX	0.00	0.00	3.97
Scavo Fossa SX	0.00	0.00	0.00
Rivestimento SX	0.00	0.00	3.97
Scavo Fossa SX	1.54	24.68	38.97

Tracciato: TR-A\_NV04B  
Sezione 2  
Progressiva: 0+020.00  
Scala: 1:200  
Quota di Riferimento: 30.00

QUOTE TERRENO		37.66	37.66	38.89	40.03	40.14	40.24
PROGRESSIVE TERRENO	-20.00	-17.37	-11.58	-8.11	0.00	5.30	15.00
QUOTE PROGETTO	38.99	38.16	37.51	37.34	37.28	37.23	40.14
DISTANZE PARZIALI PROGETTO	2.60	10.00	7.00	1.64	2.55	5.34	10.05
PROGRESSIVE PROGETTO	-20.00	-17.40	-7.00	0.00	2.10	4.82	15.00
DIFFERENZA QUOTE	1.34		-2.691				0.000

MOVIMENTI TERRA Prog. 0+020.00			
Area di sterro	65.38 m <sup>2</sup>		
Area di riparo	6.68 m <sup>2</sup>		
Volume sterro	1202.89 m <sup>3</sup>		
Volume riparo	14.79 m <sup>3</sup>		
Volume sterro cumulato	1203.69 m <sup>3</sup>		
Volume riparo cumulato	14.79 m <sup>3</sup>		
Volume netto	1278.89 m <sup>3</sup>		
TERRENO VEGETALE			
Materiale	Area	Volume	Vol. Cum.
Veghiale	2.129 m <sup>2</sup>	61.10 m <sup>3</sup>	61.10 m <sup>3</sup>
SOVRASTRUTTURA			
Materiale	Area	Volume	Vol. Cum.
Ulcure	0.354 m <sup>2</sup>	6.09 m <sup>3</sup>	6.09 m <sup>3</sup>
Binder	0.453 m <sup>2</sup>	7.81 m <sup>3</sup>	7.81 m <sup>3</sup>
Base	1.091 m <sup>2</sup>	18.26 m <sup>3</sup>	18.26 m <sup>3</sup>
Fondazione	1.364 m <sup>2</sup>	22.82 m <sup>3</sup>	22.82 m <sup>3</sup>
Supercompattato	2.729 m <sup>2</sup>	45.54 m <sup>3</sup>	45.54 m <sup>3</sup>
Cist. Ulcure	0.080 m <sup>2</sup>	1.79 m <sup>3</sup>	1.79 m <sup>3</sup>
Cist. Binder	0.188 m <sup>2</sup>	4.19 m <sup>3</sup>	4.19 m <sup>3</sup>
Cist. Sottopav.	0.054 m <sup>2</sup>	1.31 m <sup>3</sup>	1.31 m <sup>3</sup>
Pad. Ulcure	0.111 m <sup>2</sup>	2.83 m <sup>3</sup>	2.83 m <sup>3</sup>
Pad. Magrone	0.188 m <sup>2</sup>	4.71 m <sup>3</sup>	4.71 m <sup>3</sup>
Pad. Allettamento	0.188 m <sup>2</sup>	4.71 m <sup>3</sup>	4.71 m <sup>3</sup>
MANUFATTI			
Materiale	Area	Volume	Vol. Cum.
Cunette	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	0.00 m <sup>3</sup>
Magrone Cunette	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	0.00 m <sup>3</sup>
Corsoio Rotatorio	0.054 m <sup>2</sup>	0.00 m <sup>3</sup>	0.00 m <sup>3</sup>
Quantità Fossati di Guardia			
Materiale	Area	Volume	Vol. Cum.
Rivestimento SX	0.00	3.97	3.97
Scavo Fossa SX	0.00	0.00	0.00
Rivestimento SX	0.00	3.97	3.97
Scavo Fossa SX	0.00	14.30	14.30

Tracciato: TR-A\_NV04B  
Sezione 5  
Progressiva: 0+080.00  
Scala: 1:200  
Quota di Riferimento: 30.00

QUOTE TERRENO		37.66	37.73	38.39	38.22	38.01	37.65	37.45
PROGRESSIVE TERRENO	-20.00	-16.21	-9.24	-4.87	0.00	36.69	6.03	15.00
QUOTE PROGETTO	38.99	38.71	37.06	36.89	36.87	36.87	37.65	37.45
DISTANZE PARZIALI PROGETTO	2.60	10.00	7.00	1.05	1.05	0.86	4.41	10.05
PROGRESSIVE PROGETTO	-20.00	-17.40	-7.00	0.00	1.05	2.10	6.51	15.00
DIFFERENZA QUOTE	1.34		-1.119				0.000	0.000

MOVIMENTI TERRA Prog. 0+080.00			
Area di sterro	22.07 m <sup>2</sup>		
Area di riparo	5.55 m <sup>2</sup>		
Volume sterro	489.79 m <sup>3</sup>		
Volume riparo	17.00 m <sup>3</sup>		
Volume sterro cumulato	3153.30 m <sup>3</sup>		
Volume riparo cumulato	108.51 m <sup>3</sup>		
Volume netto	3044.79 m <sup>3</sup>		
TERRENO VEGETALE			
Materiale	Area	Volume	Vol. Cum.
Veghiale	1.458 m <sup>2</sup>	38.64 m <sup>3</sup>	154.23 m <sup>3</sup>
SOVRASTRUTTURA			
Materiale	Area	Volume	Vol. Cum.
Ulcure	0.322 m <sup>2</sup>	6.63 m <sup>3</sup>	40.92 m <sup>3</sup>
Binder	0.402 m <sup>2</sup>	8.29 m <sup>3</sup>	51.19 m <sup>3</sup>
Base	0.966 m <sup>2</sup>	19.81 m <sup>3</sup>	122.74 m <sup>3</sup>
Fondazione	1.207 m <sup>2</sup>	24.89 m <sup>3</sup>	153.43 m <sup>3</sup>
Supercompattato	2.414 m <sup>2</sup>	49.73 m <sup>3</sup>	306.88 m <sup>3</sup>
Cist. Ulcure	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	2.73 m <sup>3</sup>
Cist. Binder	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	6.38 m <sup>3</sup>
Cist. Sottopav.	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	1.69 m <sup>3</sup>
Pad. Ulcure	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	4.31 m <sup>3</sup>
Pad. Magrone	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	7.18 m <sup>3</sup>
Pad. Allettamento	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	7.18 m <sup>3</sup>
MANUFATTI			
Materiale	Area	Volume	Vol. Cum.
Cunette	0.231 m <sup>2</sup>	4.68 m <sup>3</sup>	4.68 m <sup>3</sup>
Magrone Cunette	0.100 m <sup>2</sup>	2.82 m <sup>3</sup>	4.57 m <sup>3</sup>
Corsoio Rotatorio	0.054 m <sup>2</sup>	0.00 m <sup>3</sup>	2.78 m <sup>3</sup>
Quantità Fossati di Guardia			
Materiale	Area	Volume	Vol. Cum.
Rivestimento SX	0.00	0.00	3.97
Scavo Fossa SX	0.00	0.00	0.00
Rivestimento SX	0.00	0.00	3.97
Scavo Fossa SX	0.00	24.68	63.65

Tracciato: TR-A\_NV04B  
Sezione 3  
Progressiva: 0+040.00  
Scala: 1:200  
Quota di Riferimento: 30.00

QUOTE TERRENO		37.66	37.61	37.56	37.45	37.20	37.34
PROGRESSIVE TERRENO	-20.00	-17.04	-13.17	-3.18	0.00	37.12	15.00
QUOTE PROGETTO	38.99	38.10	37.14	37.08	37.05	37.01	37.34
DISTANZE PARZIALI PROGETTO	2.60	10.00	7.00	3.33	1.06	7.00	13.99
PROGRESSIVE PROGETTO	-20.00	-17.40	-7.00	0.00	1.00	4.69	15.00
DIFFERENZA QUOTE	1.34		-0.153				-0.46

MOVIMENTI TERRA Prog. 0+040.00			
Area di sterro	15.19 m <sup>2</sup>		
Area di riparo	12.03 m <sup>2</sup>		
Volume sterro	871.45 m <sup>3</sup>		
Volume riparo	37.48 m <sup>3</sup>		
Volume sterro cumulato	2165.14 m <sup>3</sup>		
Volume riparo cumulato	52.28 m <sup>3</sup>		
Volume netto	2112.86 m <sup>3</sup>		
TERRENO VEGETALE			
Materiale	Area	Volume	Vol. Cum.
Veghiale	0.000 m <sup>2</sup>	32.71 m <sup>3</sup>	93.81 m <sup>3</sup>
SOVRASTRUTTURA			
Materiale	Area	Volume	Vol. Cum.
Ulcure	0.880 m <sup>2</sup>	13.79 m <sup>3</sup>	19.83 m <sup>3</sup>
Binder	1.100 m <sup>2</sup>	17.18 m <sup>3</sup>	24.79 m <sup>3</sup>
Base	2.638 m <sup>2</sup>	41.24 m <sup>3</sup>	59.50 m <sup>3</sup>
Fondazione	3.288 m <sup>2</sup>	51.55 m <sup>3</sup>	74.37 m <sup>3</sup>
Supercompattato	6.987 m <sup>2</sup>	103.11 m <sup>3</sup>	148.73 m <sup>3</sup>
Cist. Ulcure	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	2.73 m <sup>3</sup>
Cist. Binder	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	6.38 m <sup>3</sup>
Cist. Sottopav.	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	1.99 m <sup>3</sup>
Pad. Ulcure	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	4.31 m <sup>3</sup>
Pad. Magrone	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	7.18 m <sup>3</sup>
Pad. Allettamento	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	7.18 m <sup>3</sup>
MANUFATTI			
Materiale	Area	Volume	Vol. Cum.
Cunette	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	0.00 m <sup>3</sup>
Magrone Cunette	0.000 m <sup>2</sup>	0.00 m <sup>3</sup>	0.00 m <sup>3</sup>