

Tracciato: TR-A_NV144
Sezione 31
Progressiva: 0+600.00
Scala: 1:200
Quota di Riferimento: 10.00

QUOTE TERRENO	12.94	12.84	12.46	12.38	12.29	12.22
PROGRESSIVE TERRENO	-20.00	-10.42	0.00	5.76	-12.39	-18.40
QUOTE PROGETTO		12.56	12.40	12.44	12.47	12.40
DISTANZE PARZIALI PROGETTO		1.36	1.38	1.50	1.38	1.61
PROGRESSIVE PROGETTO		-4.86	-3.50	0.00	1.50	5.11
DIFFERENZA QUOTE		0.000	0.899	0.899	0.897	0.894

MOVIMENTI TERRA Prog. 6+00.00			
Area di sterno			0.00 m ²
Area di riporto			3.86 m ²
Volume sterno			0.00 m ³
Volume riporto			97.20 m ³
Volume sterno cumulato			1411.20 m ³
Volume riporto cumulato			1888.25 m ³
Volume netto			-477.05 m ³
Materiale			
Scotico	5.101 m ²	110.51 m ³	2505.43 m ³
Anticappellare	5.101 m ²	110.51 m ³	2505.43 m ³
Bonifica	4.867 m ²	85.58 m ³	1774.35 m ³
TERRENO VEGETALE			
Materiale	Area	Volume	Vol. Cum.
Vegetale	1.711 m ²	36.52 m ³	644.05 m ³
SOVRASTRUTTURA			
Materiale	Area	Volume	Vol. Cum.
Urtura	0.160 m ²	3.20 m ³	97.60 m ³
Binder	0.200 m ²	4.00 m ³	122.00 m ³
Base	0.320 m ²	6.40 m ³	193.20 m ³
Fondazione	0.600 m ²	12.00 m ³	368.00 m ³
Supercompattato	1.200 m ²	24.00 m ³	732.01 m ³
MANUFATTI			
Materiale	Area	Volume	Vol. Cum.
Cunetta	0.000 m ²	0.00 m ³	89.97 m ³
Magnone Cunetta	0.000 m ²	0.00 m ³	38.00 m ³
Corsoio	0.038 m ²	0.77 m ³	15.71 m ³
Quantità Fossi di Guardia			
Materiale	Area	Volume	Vol. Cum.
Rivestimento DX	0.00	0.00	65.04
Scavo Fossi DX	0.73	14.49	497.89

Tracciato: TR-A_NV144
Sezione 34
Progressiva: 0+660.00
Scala: 1:200
Quota di Riferimento: 10.00

QUOTE TERRENO	12.40	12.17	12.45	11.99	11.95	11.82
PROGRESSIVE TERRENO	-20.00	-11.98	-6.74	0.00	6.02	-13.00
QUOTE PROGETTO		12.35	12.83	12.75	12.69	12.75
DISTANZE PARZIALI PROGETTO		2.23	1.38	1.50	1.38	2.89
PROGRESSIVE PROGETTO		-5.73	-3.50	0.00	1.50	6.19
DIFFERENZA QUOTE		0.000	1.707	1.791	1.791	1.707

MOVIMENTI TERRA Prog. 6+60.00			
Area di sterno			0.00 m ²
Area di riporto			11.55 m ²
Volume sterno			0.00 m ³
Volume riporto			196.58 m ³
Volume sterno cumulato			1411.20 m ³
Volume riporto cumulato			2296.12 m ³
Volume netto			-883.93 m ³
Materiale			
Scotico	7.758 m ²	133.34 m ³	2864.05 m ³
Anticappellare	7.758 m ²	133.34 m ³	2864.05 m ³
Bonifica	4.159 m ²	84.80 m ³	2012.63 m ³
TERRENO VEGETALE			
Materiale	Area	Volume	Vol. Cum.
Vegetale	2.427 m ²	45.67 m ³	763.06 m ³
SOVRASTRUTTURA			
Materiale	Area	Volume	Vol. Cum.
Urtura	0.160 m ²	3.20 m ³	107.20 m ³
Binder	0.200 m ²	4.00 m ³	134.00 m ³
Base	0.320 m ²	6.40 m ³	214.40 m ³
Fondazione	0.600 m ²	12.00 m ³	402.00 m ³
Supercompattato	1.200 m ²	24.00 m ³	804.01 m ³
MANUFATTI			
Materiale	Area	Volume	Vol. Cum.
Cunetta	0.000 m ²	0.00 m ³	89.97 m ³
Magnone Cunetta	0.000 m ²	0.00 m ³	38.00 m ³
Corsoio	0.038 m ²	0.77 m ³	18.00 m ³
Quantità Fossi di Guardia			
Materiale	Area	Volume	Vol. Cum.
Rivestimento DX	0.00	0.00	65.04
Scavo Fossi DX	1.13	20.83	649.89

Tracciato: TR-A_NV144
Sezione 32
Progressiva: 0+620.00
Scala: 1:200
Quota di Riferimento: 10.00

QUOTE TERRENO	12.64	12.59	12.55	12.36	12.46	12.16
PROGRESSIVE TERRENO	-20.00	-16.85	-5.49	0.00	8.88	-12.16
QUOTE PROGETTO		12.53	13.43	13.36	13.36	12.31
DISTANZE PARZIALI PROGETTO		1.35	1.38	1.50	1.38	1.68
PROGRESSIVE PROGETTO		-4.45	-3.50	0.00	1.50	5.18
DIFFERENZA QUOTE		0.000	0.946	0.950	0.947	0.947

MOVIMENTI TERRA Prog. 6+20.00			
Area di sterno			0.00 m ²
Area di riporto			4.53 m ²
Volume sterno			0.00 m ³
Volume riporto			83.89 m ³
Volume sterno cumulato			1411.20 m ³
Volume riporto cumulato			1972.14 m ³
Volume netto			-560.94 m ³
Materiale			
Scotico	5.926 m ²	110.27 m ³	2615.69 m ³
Anticappellare	5.926 m ²	110.27 m ³	2615.69 m ³
Bonifica	3.080 m ²	79.47 m ³	1653.82 m ³
TERRENO VEGETALE			
Materiale	Area	Volume	Vol. Cum.
Vegetale	1.741 m ²	34.52 m ³	678.57 m ³
SOVRASTRUTTURA			
Materiale	Area	Volume	Vol. Cum.
Urtura	0.160 m ²	3.20 m ³	100.00 m ³
Binder	0.200 m ²	4.00 m ³	136.00 m ³
Base	0.320 m ²	6.40 m ³	201.60 m ³
Fondazione	0.600 m ²	12.00 m ³	378.00 m ³
Supercompattato	1.200 m ²	24.00 m ³	756.01 m ³
MANUFATTI			
Materiale	Area	Volume	Vol. Cum.
Cunetta	0.000 m ²	0.00 m ³	89.97 m ³
Magnone Cunetta	0.000 m ²	0.00 m ³	38.00 m ³
Corsoio	0.038 m ²	0.77 m ³	16.47 m ³
Quantità Fossi di Guardia			
Materiale	Area	Volume	Vol. Cum.
Rivestimento DX	0.00	0.00	65.04
Scavo Fossi DX	0.72	14.45	512.34

Tracciato: TR-A_NV144
Sezione 35
Progressiva: 0+680.00
Scala: 1:200
Quota di Riferimento: 10.00

QUOTE TERRENO	12.09	12.80	12.55	12.15	12.15	12.01
PROGRESSIVE TERRENO	-20.00	-13.49	0.00	6.15	6.15	-15.82
QUOTE PROGETTO		12.55	14.04	13.94	13.82	11.04
DISTANZE PARZIALI PROGETTO		2.22	1.38	1.50	1.38	2.61
PROGRESSIVE PROGETTO		-5.72	-3.50	0.00	1.50	6.52
DIFFERENZA QUOTE		0.000	1.553	1.529	1.536	1.536

MOVIMENTI TERRA Prog. 6+80.00			
Area di sterno			0.00 m ²
Area di riporto			10.25 m ²
Volume sterno			0.00 m ³
Volume riporto			218.02 m ³
Volume sterno cumulato			1411.20 m ³
Volume riporto cumulato			2513.15 m ³
Volume netto			-1101.95 m ³
Materiale			
Scotico	7.570 m ²	153.29 m ³	3617.33 m ³
Anticappellare	7.570 m ²	153.29 m ³	3617.33 m ³
Bonifica	4.678 m ²	88.37 m ³	2101.00 m ³
TERRENO VEGETALE			
Materiale	Area	Volume	Vol. Cum.
Vegetale	2.381 m ²	48.08 m ³	811.14 m ³
SOVRASTRUTTURA			
Materiale	Area	Volume	Vol. Cum.
Urtura	0.177 m ²	3.54 m ³	110.57 m ³
Binder	0.221 m ²	4.42 m ³	138.21 m ³
Base	0.353 m ²	7.06 m ³	221.13 m ³
Fondazione	0.662 m ²	13.24 m ³	414.63 m ³
Supercompattato	1.325 m ²	26.50 m ³	829.26 m ³
MANUFATTI			
Materiale	Area	Volume	Vol. Cum.
Cunetta	0.000 m ²	0.00 m ³	89.97 m ³
Magnone Cunetta	0.000 m ²	0.00 m ³	38.00 m ³
Corsoio	0.038 m ²	0.77 m ³	18.77 m ³
Quantità Fossi di Guardia			
Materiale	Area	Volume	Vol. Cum.
Rivestimento DX	0.00	0.00	65.04
Scavo Fossi DX	0.62	17.50	567.39

Tracciato: TR-A_NV144
Sezione 33
Progressiva: 0+640.00
Scala: 1:200
Quota di Riferimento: 10.00

QUOTE TERRENO	12.48	12.47	12.33	12.33	12.14	12.09
PROGRESSIVE TERRENO	-20.00	-16.82	-11.06	-5.82	9.20	-15.96
QUOTE PROGETTO		12.32	13.03	13.55	13.52	12.13
DISTANZE PARZIALI PROGETTO		1.97	1.38	1.50	1.38	2.19
PROGRESSIVE PROGETTO		-5.47	-3.50	0.00	1.50	5.69
DIFFERENZA QUOTE		0.000	1.377	1.397	1.426	1.463

MOVIMENTI TERRA Prog. 6+40.00			
Area di sterno			0.00 m ²
Area di riporto			8.11 m ²
Volume sterno			0.00 m ³
Volume riporto			126.40 m ³
Volume sterno cumulato			1411.20 m ³
Volume riporto cumulato			2098.54 m ³
Volume netto			-687.34 m ³
Materiale			
Scotico	5.539 m ²	115.91 m ³	2730.71 m ³
Anticappellare	5.539 m ²	115.91 m ³	2730.71 m ³
Bonifica	4.321 m ²	74.01 m ³	1927.83 m ³
TERRENO VEGETALE			
Materiale	Area	Volume	Vol. Cum.
Vegetale	2.140 m ²	38.82 m ³	717.38 m ³
SOVRASTRUTTURA			
Materiale	Area	Volume	Vol. Cum.
Urtura	0.160 m ²	3.20 m ³	104.00 m ³
Binder	0.200 m ²	4.00 m ³	130.00 m ³
Base	0.320 m ²	6.40 m ³	208.00 m ³
Fondazione	0.600 m ²	12.00 m ³	390.00 m ³
Supercompattato	1.200 m ²	24.00 m ³	780.01 m ³
MANUFATTI			
Materiale	Area	Volume	Vol. Cum.
Cunetta	0.000 m ²	0.00 m ³	89.97 m ³
Magnone Cunetta	0.000 m ²	0.00 m ³	38.00 m ³
Corsoio	0.038 m ²	0.77 m ³	17.24 m ³
Quantità Fossi di Guardia			
Materiale	Area	Volume	Vol. Cum.
Rivestimento DX	0.00	0.00	65.04
Scavo Fossi DX	0.95	16.72	529.06

Tracciato: TR-A_NV144
Sezione 36
Progressiva: 0+700.00
Scala: 1:200
Quota di Riferimento: 10.00

QUOTE TERRENO	12.20	12.17	12.00	12.00	12.02	12.34
PROGRESSIVE TERRENO	-20.00	-19.42	-13.00	0.00	8.57	-16.11
QUOTE PROGETTO		13.17	14.03	13.94	13.88	12.88
DISTANZE PARZIALI PROGETTO		1.29	1.38	1.50	1.38	1.48
PROGRESSIVE PROGETTO		-4.79	-3.50	0.00	1.50	5.88
DIFFERENZA QUOTE		0.000	0.848	0.904	0.883	0.854

MOVIMENTI TERRA Prog. 7+00.00			
Area di sterno			0.00 m ²
Area di riporto			3.68 m ²
Volume sterno			0.00 m ³
Volume riporto			138.29 m ³
Volume sterno cumulato			1411.20 m ³
Volume riporto cumulato			2651.44 m ³
Volume netto			-1240.24 m ³
Materiale			
Scotico	3.175 m ²	100.34 m ³	3127.27 m ³
Anticappellare	3.175 m ²	100.34 m ³	3127.27 m ³
Bonifica	4.587 m ²	89.46 m ³	2190.46 m ³
TERRENO VEGETALE			
Materiale	Area	Volume	Vol. Cum.
Vegetale	1.643 m ²	39.80 m ³	850.94 m ³
SOVRASTRUTTURA			
Materiale	Area	Volume	