



REFERENCE DOCUMENTS	
021703BZRB71008	DESIGN PREMISES
015800BZDA0005	AZALEA A - ANEMONE CL - PIPELINE FLUSHING SCHEMATIC

GEODETTIC PARAMETERS	
DATUM : ROMA 1940 ELLISSOIDE: HAYFORD 1924 Semiasse Maggiore: 6378388.00m Schiacciamento: 1/297 PROIEZIONE: GAUSS-BOAGA FUSO EST Metodo: Trasversa Mercatore Falso Est: 2520000m Falso Nord: 0m Meridiano Centrale: 15°E Fattore di Riduzione: 0.9996	DATUM SHIFT ENI (da WGS84 a ROMA 1940) Traslazione x: +223.700m Traslazione y: +67.380m Traslazione z: -1.340m Rotazione Rx: 0° Rotazione Ry: 0° Rotazione Rz: 0° Scala: 0.0ppm VERTICAL DATUM: Livello Medio Mare

- NOTES**
- ALL DIMENSIONS ARE IN METERS UNLESS OTHERWISE STATED.
 - SHOWN PIPELINE ROUTES ARE TAKEN FROM ENI GIS SYSTEM.
 - BURIAL DEPTHS OF THE PIPELINES TO BE DECOMMISSIONED ARE TAKEN FROM AZALEA A - ANEMONE CL SURVEY FINAL REPORT, IDP AM791, DELIVERY DATE 14/06/2019.
 - BATHYMETRY AND SEABED MORPHOLOGY ARE TAKEN FROM AM462 AZALEA A BOTTOM SURVEY.

LEGEND

	Centre of well (Eni database co-ordinates)		Exposed Pipeline
	ANEMONE CL Platform		Pipeline to be decommissioned (Buried depth in meters)
	Bathymetry (referred to M.S.L.)		Buried Pipeline (Buried depth in meters)
	Massive and even debris area		Trawling scars
	Area affected by gas		Kilometer Point



Facilities									
Description	Company	Platform Typology	Structure Typology	Water Depth	Date of Installation	Gauss Boaga Est		Roma 40	
						North	East	Latitude	Longitude
Azalea A	Eni	Single	Monopod	19.2 m	1984	4893514.92	2337282.65	44° 10' 16.230" N	12° 42' 52.329" E
Anemone CL	Eni	Multiple	Monopod	22 m	1979	4898071.76	2336679.49	44° 12' 43.257" N	12° 42' 19.464" E

Pipelines Data									
No.	Description	Wall Thickness	Design Pressure	Material	Corrosion Allowance	Date of Installation	Fluid	Outside Diameter	
1	Azalea A - Anemone CL	10.97 mm	215.75 bara	API 5L-Gr.B	not available	1978	Gas	6"	
2	Azalea A - Anemone CL	4.78 mm	130.42 bara	API 5L-X52	not available	1978	Glycol	3"	

PR-DE	01	22/08/2019	Final Issue	Project Team	M. Mastai	S. Sartirana	M. Proverbio	Eni
Validity	Revision	Date	Description	Prepared	Checked	Approved	Authorised	Company Approved
Company Logo and Business Name				Project Name		Company Document ID:		
enl				DECOMMISSIONING OFFSHORE ITALIA		015800BZDC00006		
Facility and SubFacility Name				Scale		Sheet of Sheets		
DECOMMISSIONING OFFSHORE ITALIA				1:1500 @A1		1/1		
Document Title				Superseded by N.		Unit		
AZALEA A - ANEMONE CL PIPELINES ROUTE				n.a.		n.a.		