

**THREE-PHASE  
TRANSFORMERLESS  
1,500 V STRING  
INVERTER WITH  
THE MAXIMUM  
POWER DENSITY**

## INGECON® SUN 160TL

A three-phase inverter family for commercial, industrial and utility-scale PV plants.

### Greater cost-effectiveness

Thanks to its greater output power (up to 160 kW if connected to a 690 Vac network), the new INGECON® SUN 160TL allows to drastically reduce the number of inverters required for designing a PV power plant. Thus, it minimises the labour cost and reduces the global cabling cost. Furthermore, it enables up to a 20% cost reduction in AC cabling as this PV inverter does not require a neutral wire.

Moreover, it does not require DC combiner boxes, nor AC combiner boxes, ensuring the minimum possible CAPEX (Capital Expenditures).

Furthermore, its string inverter philosophy permits an easy and immediate replacement that does not require qualified technicians.

### Higher flexibility and power density

The highest flexibility thanks to its maximum DC voltage (1,500 V) and to its wide voltage range MPP (576-1,250 V). Awesome power density, with up to 161 kW in a 75 kg inverter.

### Rugged design

Aluminium casing, especially conceived for indoor and outdoor applications (IP65). The INGECON® SUN 3Play TL inverters have been designed to guarantee a long life expectancy and to withstand extreme temperatures.

### Advanced communications as standard

Thanks to the Wi-Fi communication that this inverter integrates, the power plant can be monitored and controlled without any additional communication cabling. Moreover, it also integrates Ethernet communication. These features, together with the webserver that the inverter integrates, enable a fast and reliable commissioning using a mobile phone, a tablet or a laptop. Furthermore, it is compatible with external Cloud Connect software.

**Standard 5 year warranty, extendable for up to 25 years**



# 160TL

## Fully equipped

The 1,500 V series within the INGECON® SUN 3Play inverter family is supplied fully equipped with the main electric protections, aiming to reach the maximum performance with the greatest cost-effectiveness.

### Integrated features

	STD version	PRO version
DC inputs terminal Block	✓	
PV fast connectors <sup>(1)</sup>		✓
DC switch	✓	✓
DC surge arresters (type I+II)	✓	✓
AC surge arresters (type II)	✓	✓
DC fuses		✓ <sup>(2)</sup>
Strings current metering kit		✓
Wi-Fi and Ethernet communications	✓	✓

**Notes:** <sup>(1)</sup> No crimping tool needed <sup>(2)</sup> 32A fuses. Only for the positive pole. Optionally, DC fuses for the negative pole also available.

### MAIN FEATURES

- Low-voltage ride-through capability.
- Reactive power capability.
- Compatible with external Cloud Connect software.
- 99.1% maximum efficiency.
- Ethernet and Wi-Fi communications supplied as standard.
- Integrated Webserver.
- Software INGECON® SUN Monitor for PV plant monitoring.
- Suitable for indoor and outdoor installations (IP65).
- High temperature performance.

- Different versions to satisfy every project needs.
- 3 digital inputs and 2 digital outputs.
- DRMO Input Ready (for the Australian market).

### PROTECTIONS

- Shortcircuits and overloads at the output.
- Anti-islanding with automatic disconnection.
- Insulation faults.
- AC overvoltages with type 2 surge arresters.
- DC overvoltages with type 1+2 surge arresters.
- 32A DC fuses (PRO version).


### OPTIONAL ACCESSORIES

- Self-consumption kit.
- RS-485 communication.
- DC fuses for the negative pole.
- Compatibility with night power supply.

### BENEFITS

- Greater power density.
- Greater cost-effectiveness thanks to the cabling cost reduction.
- High availability compared to central inverters.
- High efficiency rates.
- Easy maintenance.


## INGECON® SUN 160TL PRO version




160TL						
<b>Input (DC)</b>						
Recommended PV array power range	95 - 136 kWp	113 - 162.5 kWp	141 - 203 kWp	148 - 213 kWp	153.5 - 220 kWp	162 - 233.5 kWp
MPP Operating voltage range <sup>(1)</sup>	576 - 1,250 V	692 - 1,250 V	864 - 1,250 V	908 - 1,250 V	936 - 1,250 V	994 - 1,250 V
Maximum voltage <sup>(2)</sup>	1,500 V					
Maximum current <sup>(3)</sup>	168 A					
Short-circuit current	250 A					
Inputs (STD / PRO)	1 / 20					
MPPT	1					
<b>Output (AC)</b>						
Rated power at 25 °C / 40 °C / 50 °C	92.8 kW / 85.9 kW / 83.8 kW	111.4 kW / 103.1 kW / 100.6 kW	139.3 kW / 128.9 kW / 125.8 kW	146.2 kW / 135.3 kW / 132 kW	150.9 kW / 139.6 kW / 136.2 kW	160.1 kW / 148.2 kW / 144.6 kW
Maximum current at 25 °C / 40 °C / 50 °C	134 A / 124 A / 121 A					
Rated voltage	400 V	480 V	600 V	630 V	650 V	690 V
Frequency	50 / 60 Hz					
Type of grid	IT					
Power Factor	1					
Power Factor adjustable <sup>(4)</sup>	Yes, 0 - 1 (leading / lagging)					
THD (Total Harmonic Distortion) <sup>(5)</sup>	<3%					
<b>Efficiency</b>						
Maximum efficiency	99.1%					
Euroefficiency	98.7%					
<b>General Information</b>						
Refrigeration system	Forced ventilation					
Air flow	570 m <sup>3</sup> /h					
Stand-by consumption	20 W					
Consumption at night	1 W					
Ambient temperature	-25 °C to 60 °C					
Relative humidity (non-condensing)	0 - 100%					
Protection class	IP65 / NEMA 4					
Residual current monitoring unit	Yes					
Max. operating altitude	4,000 m					
Connection	AC: Max. Cross section: 240 mm <sup>2</sup> (one wire). DC connection (PRO): 6 mm <sup>2</sup> (20 pairs of PV connectors). Copper and Aluminium cabling permitted for DC and AC					
Marking	CE					
EMC and safety standards	EN 61000-6-1, EN 61000-6-2, EN 61000-6-3, EN 61000-6-4, EN 61000-3-2, EN 61000-3-3, EN 61000-3-11, EN 61000-3-12, EN 62109-1, EN 62109-2, IEC62103, EN 50178, FCC Part 15, IEC60068-2-1:2007, IEC60068-2-2:20007, IEC60068-2-14:2009, IEC60068-2-30:2005, IEC62116, IEC61683 y EN50530					
Grid connection standards	DIN V VDE V 0126-1-1, Arrêté du 23 avril 2008, EN 50438, EN 50439, EN 50549, CEI 0-21, CEI 0-16 VDE-AR-N 4105:2011-08, G59/3, P.O.12.3, AS4777.2, BDEW, IEC 62116, IEC 61727, UNE 206007-1, ABNT NBR 16149, ABNT NBR 16150, Brazilian Grid Code, South African Grid Code, Chilean Grid Code, DEWA 2.0, Jordanian Grid Code, Thailand MEA & PEA requirements					

**Notes:** <sup>(1)</sup> V<sub>mpp,min</sub> is for rated conditions (V<sub>ac</sub>=1 p.u. and Power Factor=1). V<sub>mpp,min</sub> will depend on the grid voltage (V<sub>ac</sub>), according to this relation: V<sub>mpp,min</sub>=1.44\*V<sub>ac</sub>  
<sup>(2)</sup> The inverter does not start operating until V<sub>dc</sub> < 1,450 V <sup>(3)</sup> The maximum current per PV connector is 20 A for the PRO version <sup>(4)</sup> Extended adjustment range for nominal working points <sup>(5)</sup> For rated AC power and voltage in accordance with IEC 61000-3-4 .

**Efficiency INGECON® SUN 160TL** [600 Vac] V<sub>dc</sub> = 1,075 V



**Size and weight (mm)**



**160TL STD**  
75 kg.

**160TL PRO**  
78 kg.



# Ingeteam

**Ingeteam Power Technology, S.A.**  
Avda. Ciudad de la Innovación, 13  
31621 Sarriguren (Navarra) - Spain  
Tel.: +34 948 288 000  
Fax: +34 948 288 001  
e-mail: solar.energy@ingeteam.com

**Ingeteam S.r.l.**  
Via Emilia Ponente, 232  
48014 Castel Bolognese (RA) - Italy  
Tel.: +39 0546 651 490  
Fax: +39 054 665 5391  
e-mail: italia.energy@ingeteam.com

**Ingeteam SAS**  
La Naurouze B - 140 rue Carmin  
31670 Labège - France  
Tel.: +33 (0)5 61 25 00 00  
Fax: +33 (0)5 61 25 00 11  
e-mail: france@ingeteam.com

**Ingeteam INC.**  
3550 W. Canal St.  
Milwaukee, WI 53208 - USA  
Tel.: +1 (414) 934 4100 / +1 (855) 821 7190  
Fax: +1 (414) 342 0736  
e-mail: solar.us@ingeteam.com

**Ingeteam, a.s.**  
Technologická 371/1  
70800 Ostrava - Pustkovec  
Czech Republic  
Tel.: +420 59 747 6800  
Fax: +420 59 732 6899  
e-mail: czech@ingeteam.com

**Ingeteam Shanghai, Co. Ltd.**  
Shanghai Trade Square, 1105  
188 Si Ping Road  
200086 Shanghai - P.R. China  
Tel.: +86 21 65 07 76 36  
Fax: +86 21 65 07 76 38  
e-mail: shanghai@ingeteam.com

**Ingeteam, S.A. de C.V.**  
Leibnitz Ext 13 Int 1102, Colonia Anzures  
11590 - Miguel Hidalgo  
Ciudad de México - Mexico  
Tel.: +52 81 8311 4858  
Fax: +52 81 8311 4859  
e-mail: northamerica@ingeteam.com

**Ingeteam Ltda.**  
Rua Estácio de Sá, 560  
Jd. Santa Genebra  
13080-010 Campinas/SP - Brazil  
Tel.: +55 19 3037 3773  
e-mail: brazil@ingeteam.com

**Ingeteam Pty Ltd.**  
Unit 2 Alphen Square South  
16th Road, Randjiespark  
Midrand 1682 - South Africa  
Tel.: +2711 314 3190  
Fax: +2711 314 2420  
e-mail: southafrica@ingeteam.com

**Ingeteam SpA**  
Los militares 5890, Torre A, oficina 401  
7560742 - Las Condes  
Santiago de Chile - Chile  
Tel.: +56 2 29574531  
e-mail: chile@ingeteam.com

**Ingeteam Power Technology India Pvt. Ltd.**  
2nd Floor, 431  
Udyog Vihar, Phase III  
122016 Gurgaon (Haryana) - India  
Tel.: +91 124 420 6491-5  
Fax: +91 124 420 6493  
e-mail: india@ingeteam.com

**Ingeteam Sp. z o.o.**  
Ul. Koszykowa 60/62 m 39  
00-673 Warszawa - Poland  
Tel.: +48 22 821 9930  
Fax: +48 22 821 9931  
e-mail: polska@ingeteam.com

**Ingeteam Australia Pty Ltd.**  
iAccelerate Centre, Building 239  
Innovation Campus, Squires Way  
North Wollongong, NSW 2500 - Australia  
Tel.: +61 429 111 190  
e-mail: australia@ingeteam.com

**Ingeteam Panama S.A.**  
Av. Manuel Espinosa Batista,  
Ed. Torre Internacional  
Business Center, Apto./Local 407  
Urb.C45 Bella Vista  
Bella Vista - Panama  
Tel.: +50 761 329 467

**Ingeteam Service S.R.L.**  
Bucuresti, Sector 2,  
Bulevardul Dimitrie Pompeiu Nr 5-7  
Cladirea Hermes Business  
Campus 1, Birou 236, Etaj 2  
Romania  
Tel.: +40 728 993 202

**Ingeteam Philippines Inc.**  
Office 2, Unit 330, Milelong Bldg.  
Amorsolo St. corner Rufino St.  
1230 Makati  
Gran Manila - Philippines  
Tel.: +63 0917 677 6039

**Ingeteam Power Technology, S.A.**  
Level 1, Al Bateen Tower C6 Bainunah  
ADIB Building, Street 34  
PO BOX 30010 - Abu Dhabi  
United Arab Emirates  
Tel.: +971 50 125 8244

**Ingeteam Vietnam Ltd.**  
Spaces - 28A Tran Hung Dao Street  
Phan Chu Trinh Ward  
Hoan Kiem District  
Ha Noi City - Vietnam  
Tel.: +84 24 71014057  
e-mail: vietnam@ingeteam.com

**Ingeteam Uruguay, S.A.**  
Avenida 18 de Julio, 1474, Piso 12  
11200, Montevideo - Uruguay  
Tel.: +598 934 92064