



Tabella materiale: Scotico

Progressiva	Area (m²)	Volume (m³)	Vol. cum. (m³)
0+000.00	4.05	0.00	0.00
0+020.00	2.61	66.14	66.14
0+040.00	2.86	54.68	120.82
0+049.69	4.49	35.29	156.19
0+063.54	33.87	234.09	390.19
0+080.00	26.21	493.08	882.27
0+100.00	29.49	556.75	1440.02
0+120.00	32.14	616.17	2056.20
0+130.50	32.96	341.82	2398.12

Tabella materiale: Scavo

Progressiva	Area (m²)	Volume (m³)	Vol. cum. (m³)
0+000.00	2.54	0.00	0.00
0+020.00	0.02	16.98	16.98
0+040.00	0.00	0.11	17.09
0+049.69	1.10	1.88	20.97
0+063.54	42.97	221.17	242.14
0+080.00	102.49	1769.25	2011.39
0+100.00	120.76	2217.85	4229.24
0+120.00	159.88	2880.81	7110.05
0+130.50	168.57	1230.20	8340.25

Tabella materiale: Rilevato