




**PROGETTAZIONE DEFINITIVA E STUDIO DI IMPATTO AMBIENTALE  
PER RICHIESTA DI AUTORIZZAZIONE UNICA  
DELL'IMPIANTO AGRIVOLTAICO DA 40 MW  
IN ZONA INDUSTRIALE DI PRATO SARDO NEL COMUNE DI NUORO (NU)**

# PROGETTO DEFINITIVO

**NUORO  
SOLAR** 

COMMITTENTE:

PROGETTISTA:



TITOLO ELABORATO:

**BROCHURE TRACKER**

ELABORATO n°:  
BI029F-D-NUO-SH-01-r00

NOME FILE:

SCALA: ----

DATA: Giugno 2023

REVISIONE	N.	DATA	DESCRIZIONE	ELABORATO	CONTROLLATO	APPROVATO
	00		Giugno 2023	Prima Emissione	E. Guiot	M. Sandri
01						
02						
03						
04						

# MONOLINE<sup>+</sup>

## 2P



ADAPTED TO **XXL MODULES**



IN-HOUSE **MANUFACTURING**  
\* providing local content if required



**BIFACIAL OPTIMIZED**



**TERRAIN RESPONSE**



**PV CLEANER TESTED**  
Certified by module manufacturer



MADE WITH **MAGNELIS<sup>®</sup>**  
\* Optional



## General specifications

Tracker	Independent-row, horizontal single-axis
Maximum length	70 m.
Maximum width	5 m.
Module configuration	2 modules in portrait
Rotational range	E-O: +/- 60°
Motor per MWp	Depending on the size, the type of the module and the number of modules per string, 3 motors per row. (Maximum 70 meters length)
Ground cover ratio	30-50%
Modules supported	All market available modules
Slope tolerance	N-S: up to 23.5% every 20 m. E-W: unlimited
Module attachment	By bolts and nuts, rivet or clamps for frameless modules
Allowable wind load	Tailored to site specific condition
Wind alarm	Controlled by ultrasonic anemometer
Prepared for XXL modules	

## Communications & Control

Solar tracking method	Astronomical algorithm
Control System	Central control unit connected to plant SCADA Redundant wireless gateways to guarantee communication Self-powered DC Motor Drive Box with auxiliary panel
SCADA interface	Modbus TCP or OPC-UA
Communication	Wireless (LoRa)
Nighttime stow	Configurable
Advanced Algorithms	Adaptative Backtracking 3D & Diffuse Light Optimization (optional)

## Installation & Services

On-site training and commissioning	
Warranty	Structure: 10 years Electromechanical components: 5 years
PV Cleaner	Optional
Certifications	UL 3703, IEC 62817 on going



# MONOLine<sup>+</sup>

2P

IN-HOUSE  
**MANUFACTURING**


\* providing local content if required



ADAPTED TO  
**XXL** MODULES



TERRAIN  
**RESPONSE**



**BIFACIAL**  
OPTIMIZED



MADE WITH  
**Magnelis®**  
\*Optional



**PV CLEANER**  
TESTED

Certified by module manufacturer



## GENERAL SPECIFICATIONS

Tracker	Independent-row horizontal single-axis
Maximum length	70 m.
Maximum width	5 m.
Module configuration	2 modules in portrait
Rotational range	E-W: +/- 60°
Motor per MWp	Depending on the size, the type of the module and the number of modules per string. 3 motors per row. (Maximum 70 meters length)
Ground cover ratio	30-50%
Modules supported	All market available modules
Slope tolerance	N-S: up to 23.5% every 20 m. E-W: unlimited
Module attachment	By bolts and nuts, rivet or clamps for frameless modules
Allowable wind load	Tailored to site specific condition
Wind alarm	Controlled by ultrasonic anemometer
Prepared for XXL modules	

## COMMUNICATIONS & CONTROL

Solar tracking method	Astronomical algorithm
Controller electronics	Central control unit conneted to plant SCADA  Redundant wireless gateways to guarantee communication  Self-powered DC Motor Drive Box with auxiliary panel
SCADA interface	Modbus TCP or OPC UA
Communication Network	Wireless (LoRaWAN)
Nighttime stow	Configurable
Backtracking & diffuse sensors	Adaptative Backtracking 3D & Diffuse Light Optimization (optional)

## INSTALLATION & SERVICE

### On-site training and commissioning

### Warranty

Structure: 10 years  
Electromechanical components: 5 years

### PV Cleaner Optional

Certifications UL 3703, IEC 62817

